## BANGALORE DIVISION.

*Abstract Notification dated 30th March 1940.*

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for restoring Balgere Tank Register No. 101 of Nelamangala Taluk, published in pages 708-711 of Part VI of the *Mysore Gazette*, dated 4th April 1940.

The last date for the receipt of the tender is 2 P.M., on 19th April 1940. Duplicate challan for having credited the deposit amount of Rs. 200 into the Treasury under 17 (*a*) P. W. Deposits should accompany each tender.

N. LAKSHMINARASIMIAH,
*Executive Engineer.*

## KOLAR DIVISION.

*Abstract Notification dated 29th March 1940.*

The attention of the public is invited to the detailed notification, dated 28th March 1940, published on pages 711-714, Part VI of the *Mysore Gazette*, dated 4th April 1940, *re* tenders for restoring Purahalli Devarkere, unrestored, Major Tank, Register No. 257/681 of Kolar Taluk.

The last date for lodging of tender is 22nd April 1940 up to 2 P.M.

C. R. IYENGAR,
*Executive Engineer.*

## MANDYA DIVISION, MANDYA.

*Abstract Notification dated 30th March 1940.*

The attention of the public is hereby invited to the Notification on pages 750-753, Part VI of the issue of the *Mysore Gazette*, dated 4th April 1940, inviting tenders for Restoring Thenginaghatta Minor Tank, Register No. 1137, Krishnarajpet Taluk.

The last date fixed for the receipt of tenders in this office is 12 NOON on 22nd April 1940.

B. S. NARASINGA RAO,
*Executive Engineer.*

## HASSAN DIVISION.

*Abstract Notification dated 26th March 1940.*

The attention of the public is invited to Notification calling for tenders for "Constructing Electrical Buildings at Saklespur" published in pages 714-717, Part VI of the *Mysore Gazette*, dated the 4th April 1940.

The last date of submission of tenders is 12th April 1940.

P. SUBBA RAO,
*Executive Engineer.*

## SHIMOGA DIVISION.

*Notification dated 2nd April 1939.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 27th April 1940, for the Extension of McGann Hospital at Shimoga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four for each form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury challan of Rs. 1,720 credited to the Treasury to 17(*a*) P. W. Deposits, as earnest money, and be superscribed "Tender for Extension of McGann Hosptal at Shimoga in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Government who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words, as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy brand cement should be used for the work.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards security deposits.

Abstract estimate for extension of McGann Hospital at Shimoga (Rear extension).

| No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| 1 | Earthwork excavation of foundation in gravelly soil and filling in basement, etc., complete | C.yds. | 0 4 0 | 368 | |
| 2 | Stone jelly concrete in lime mortar (1 : 2 : 4) .. | C.ft. | 0 4 6 | 3,510 | |
| 3 | Size stone in lime mortar with bond stones 6′ apart .. .. .. .. .. | C.ft. | 0 6 6 | 9,347 | |
| 4 | Burnt stone slabs 6″ thick one line dressed and fixed in mortar with 3″ projection .. .. | S.ft. | 0 14 0 | 1,511 | |
| 5 | Burnt stone slabs 6″ thick, two line dressed and fixed in mortar .. .. .. | S.ft. | 1 0 0 | 770 | |
| 6 | Cement pointing to basement .. .. | Sqr. | 4 0 0 | 12·94 | |
| 7 | Burnt brick in mortar superstructure .. | C.ft. | 0 4 6 | 10,156 | |
| 8 | (*a*) Burnt stone slabs 6″ roughly dressed and fixed .. .. .. .. | S.ft. | 0 12 0 | 1,910 | |
| | (*b*) Providing and fixing cement concrete slabs 6′ thick .. .. .. .. | C.ft. | 0 12 0 | 81 | |
| 9 | Teakwood doors with frames of 5″×4″ with top ventilators ½ panelled and ½ glazed with pin headed moraco glass 1½″ thick shutters with parlimentary hinges brass fittings, etc., complete .. .. .. .. | S.ft. | 2 8 0 | 585 | |
| 10 | Teakwood doors with panelled shutters for W.C. with necessary iron fittings, etc., complete. | S.ft. | 1 8 0 | 63 | |
| 11 | Teakwood windows fully glazed shutters with top ventilators parlimentary hinges, etc., complete .. .. .. .. .. | S.ft. | 2 4 0 | 1,365 | |
| 12 | Teakwood glazed ventilators over doors and windows, etc. .. .. .. .. | S.ft. | 1 8 0 | 428 | |
| 13 | Providing R.C.C. chajjas of sufficient thickness and necessary reinforcements over windows in rear .. .. .. .. | S.ft. | 0 8 0 | 2,034 | |
| 14 | Providing and fixing R.S. girders 14″×5½″×40 lbs. including cost of hoisting, etc., complete with bed slabs, etc., complete .. .. | Cwt. | 15 0 0 | 181 | |
| 15 | Boxing girders with cement concrete including ½″ cement plastering, etc., complete .. .. | R.ft. | 0 10 0 | 460 | |
| 16 | Plastering with lime mortar .. .. .. | Sqr. | 3 4 0 | 146·62 | |
| | (*a*) Green coloured dado with ½″ thick cement plastering 1 : 3 and plastering ⅛″ thick coloured cement rendering .. .. | Sqr. | 18 0 0 | 8·04 | |
| | (*b*) Red coloured cement skirting with ½″ thick cement mortar 1 : 3 plastering ⅛″ thick coloured red oxide rendering, etc., complete. | Sqr. | 15 0 0 | 9·74 | |
| | (*c*) Shell lime plaster .. .. .. .. | Sqr. | 15 0 0 | 8·39 | |

| No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | |
| 17 | Exmet partition wall 4½″ thick with burnt brick in cement mortar 1 : 3 including plastering with cement mortar 1 : 4 reinforcement in every third course, etc., complete | S.ft. | 0 12 0 | 819 | |
| 18 | R.B.C. terrace of sufficient thickness and necessary reinforcement as per design, etc., complete | Sqr. | 75 0 0 | 60·62 | |
| 19 | Plain parapet walls 9″ thick, 2′ high as per design including plastering, etc., complete | R.ft. | 1 0 0 | 471 | |
| 20 | White and colour washing, two coats | Sqr. | 0 4 0 | 146·62 | |
| 21 | Flooring with stone jelly concrete in lime mortar 3″ thick 1½″ cement concrete top and plastering with red cement including expansion joints at 10′ apart, etc., complete as per specifications | Sqr. | 20 0 0 | 62·48 | |
| 22 | Painting with silicate paint, two coats | Sqr. | 4 6 0 | 37·05 | |
| 23 | Varnishing with best Gopal Varnish, two coats | Sqr. | 3 8 0 | 15·90 | |
| 24 | Burnt brick in cement mortar 1 : 2 for circular pillars as per existing design, plastering, etc., complete | Each | 25 0 0 | 26 | |
| 25 | Providing and fixing double R.S. girders 3″×6″ ×12 lbs. including hoisting, etc., over pillars of verandah | Cwt. | 15 0 0 | 42·4 | |
| 26 | Boxing the double girders with burnt brick in cement mortar with distant pipes and plastering the wire net with cement, etc., complete | R.ft. | 0 8 0 | 396 | |
| 27 | Providing, fixing and hoisting steel trusses for 20′ span as per existing design, 9′ apart with bed plates, etc., complete | Each | 100 0 0 | 4 | |
| 28 | Teakwood wrought and put up with wood oiling, etc., complete | C.ft. | 4 4 0 | 104·55 | |
| 29 | Roofing with 1st class Mangalore tiles on teak reepers with ceiling tiles, etc. | Sqr. | 30 0 0 | 19·20 | |
| 30 | Ridge tiles set in mortar and cement pointed. | R.ft. | 0 10 0 | 60 | |
| 31 | Teakwood eave boards 9″ wide as per design with painting | R.ft. | 0 8 0 | 120 | |
| 32 | Mortar bands over roof | R.ft. | 0 4 0 | 120 | |
| 33 | Teakwood finials and pendents | Each | 2 0 0 | 6 | |
| 34 | Constructing cement concrete "U" shaped drain alround | R.ft. | 0 12 0 | 500 | |
| 35 | Providing underground drains for outlet of water in courtyard | L. S. | 200 0 0 | | |
| 36 | Dismantling the sides of old walls for joining the new wall and reconstructing with bond° slabs, etc. | L. S. | 35 0 0 | | |
| 37 | Earthwork levelling, grounding and forming | L. S. | 35 0 0 | | |
| 38 | Providing C.I. Rainwater pipes 4″ dia. including bends, heads, clamps, etc., complete | R.ft. | 1 8 0 | 200 | |

D. A. HUKERI,
*Executive Engineer.*

## KADUR DIVISION.

*Abstract Notification dated 26th March 1940.*

The attention of the public is invited to the notification, published on pages 718-720, Part VI of the *Mysore Gazette*, dated 4th April 1940, calling for tenders for the work of improvements to entrance to Chikmagalur Town by widening the road and bridge across waste weir in 8/153 of Kadur-Mangalore Road at Chikmagalur.

The last date of receipt of tender in this office is 15th April 1940.

M. A. RAMANUJAM,
*Executive Engineer.*